



STEVE TSHWETE

LOCAL MUNICIPALITY

Your ref. Q08.03.11

Telephone (013) 249 7000

Fax (013) 243 2550

Our ref. Marius Britz x7376

P.O. Box 14

MIDDELBURG, MPUMALANGA

2011-03-08

1050

e-mail : mbritz@stevetshwetelm.gov.za

www.stevetshwetelm.gov.za

QUOTATION FOR PARTIALLY SUPPLY AND INSTALLATION OF 110MM COMMUNICATION CABLE PIPES AND PRECAST CONCRETE MAN HOLES

Steve Tshwete Local Municipality requires formal written quotations from registered service providers to dig trenches for a 110mm pipe, 600mm deep, and install man holes as indicated on the sketch. Here are the specifications:

- **Intended use of the communication cable pipes:**
 - The Municipality wish to upgrade the communication network that links the main building with the Library, 24Hr Centre and the Testing Station.
 - The pipe will be used as the protective path for all communication cables to the various sites.

- **Detailed requirements (you may also quote on equivalent items where Makes and Models are mentioned):**
 - **The pipes must be collected by the service provider from the Municipal Stores on the corner of Walter Sisulu and Protea Streets. Each pipe is 6m long and there will be 26 pipes that need to be transported to the Civic Centre.**
 - The service provider will have to dig trenches 600mm deep for all the pipes (supplied by the Municipality) shown on the sketch. Added together the total length is 141.6m. It will be calculated at 26 x 6m = 156m to leave room for small changes.
 - The service provider will dig holes (600 x 600 x 600) for the precast concrete man holes (supplied by the service provider). There are a total of 8 man holes on the path.
 - After all the trenches and holes are ready, all the pipes must be fitted together and placed in the trenches. There will be some connection points that the pipes will need to connect to. All the connections will be supplied by the Municipality.
 - After the pipes are in place, the precast man holes must be cut with a diamond blade and an angle grinder (for the pipes to fit) and placed in the holes. All man holes must be level.

- All the open trenches and holes and paving ($\pm 1\text{m} \times 1\text{m}$) must be closed again.
 - Draw ropes must be included in each section. The ropes must be nylon and at least 6mm in width. The rope in each section must be twice as long as the section. Each end must be secured at the end of the pipe that it won't accidentally be drawn in the pipe. The following draw ropes must be catered for:
 - 21m section - 42m rope
 - 9m section - 18m rope
 - 35.5m section - 71m rope
 - 15.6m section - 32m rope
 - 26m section - 52m rope
 - 29.5m section - 60m rope
 - Section A - 30m rope
 - Section B - 80m rope
 - Section C - 20m rope
 - Large areas of the trenching will be done by hand to minimise damage to other pipes and cables in the same area.
- **Delivery instructions:**
 - The 110mm pipes must be delivered from the Municipal stores to the Civic Centre by the service provider. Each pipe is 6m in length and the total number of pipes is 26 pipes.
 - The 600 x 600 man holes with lids must be delivered to the Civic Centre on the day of installation.
 - No space is available for storage of any material at the Civic Centre. Only material that will be installed for a specific day must be delivered at the Civic Centre.
- **When:**
 - Trenching and digging must start within 14 days after the order was issued by the Steve Tshwete Municipal Stores.
 - A site meeting will be held at the Civic Centre one day prior to the start of the project.
 - The project must be completed within one week after the project has started.
 - The Testing station section (29.5m with 2 x man holes) must be done on a weekend, starting Friday afternoon after 13:30. This is to minimise injury to the many people who visit the testing station during office hours.
- **Responsibilities:**
 - The successful supplier will be responsible for:
 - The trenching and installation of the 110mm pipes as well as the man holes on the project.
 - Installation of draw ropes in all the sections.
 - The safety of anyone who will be walking in the area to prevent them from falling into trenches and holes.
 - Marking of dangerous trenches for the public to avoid. Marking will be done with danger tape.
 - Closing of all holes and trenches and paving ($\pm 1\text{m} \times 1\text{m}$).
 - Return any unused pipes to the Municipal Stores.

- **Method of acquisition:**
 - The supply and installation of the project will be purchased from the supplier and it will become the asset of the Steve Tshwete Local Municipality.
 - Full payment for the project will be done 30 days after the invoice was handed to the Municipal Stores.

- **Pricing schedule:**
 - Please write your quotation on a company letterhead in the following format:

Item	Item Order Code	Quantity	Total Excl VAT	Vat	Total Incl VAT
Deliver and installing 110mm pipes, trenching and closing		156m (26 x 6m)			
Supply and install of man holes		8			
Supply and install draw ropes		405m			
Sundries		1			R1000
			Total		

GENERAL NOTES:

1. Written quotations should be submitted to the office of the Corporate Services, room C318, Second Floor, Civic Centre, Wanderers Avenue, Middelburg not later than 12:00 on the **15th of March 2011**.

2. The following requirement(s) apply to all prospective service providers:
 - Service providers not registered with council must log on to www.stevetshwetelm.gov.za or visit Mr Martha Mtsweni (Tel: 013-249 7309) at the Municipal Stores at Corner Protea and Walter Sisulu Street, Middelburg, Mpumalanga to get the application forms and submit a completed enlistment application before submitting the quotation.
 - Quotes should be accompanied by:
 1. **A valid tax clearance certificate**
 2. **BEE ownership stated on a letterhead**
 3. **Proof of company physical address**

For any queries, please contact **Marius Britz**, telephone **013 249 7376 / 082 895 8743**.